

DRAINAGE STUDY
for
IONE BAND OF MIWOK INDIANS
CASINO PROJECT


Prepared for:

ANALYTICAL ENVIRONMENTAL SERVICES
2021 N Street, Suite 200
Sacramento, CA 95814

Prepared by:

GENE E. THORNE & ASSOCIATES, INC.
3025 Alhambra Drive, Suite A
Cameron Park, CA 95682-7999


GENE E. THORNE, RCE 20462



January, 2004

DRAINAGE STUDY
FOR
LONE BAND OF MIWOK INDIANS CASINO PROJECT

The Lone Band of Miwok Indians Casino Project encompasses approximately 216 acres, located on the east side of Highway 49, south of the City of Plymouth, in Amador County, California. The majority of the site is currently undeveloped, although there is an established commercial strip adjacent to the Highway.

The project area contributes to two distinct watersheds. Approximately 101 acres in the central portion of the site consist of mildly sloping grassland with scattered trees and brush. This area drains from south to north into Little Indian Creek. An existing on-site pond provides limited detention for a portion of the runoff. Little Indian Creek has its origin in approximately 100 acres of off-site watershed area on the west side of Highway 49. The Creek crosses the highway onto the project, thence flows northerly in a channel that roughly parallels Highway 49. Site runoff enters Little Indian Creek at several locations. The combined flow crosses Highway 49 just north of the project. The eastern and southern project perimeters are more steeply sloped, and support growths of heavy brush and/or trees. The perimeter area can be divided into seven relatively small shed areas tributary to Dry Creek. The Dry Creek channel, flowing in a southeasterly direction, is located off-site, to the south of the project.

Details of proposed site development are unknown at the time this drainage study is being completed. For purposes of the analysis, it is assumed that slope constraints preclude development within the Dry Creek sheds. It is assumed that the project area within the Little Indian Creek watershed will be fully developed, and will utilize storm drain pipes to collect and convey runoff across the project area to the existing point of discharge of Little Indian Creek near the northern project boundary. On-site storm water detention is provided for the purpose of peak flow mitigation.

The drainage study was completed in adherence to current practices utilizing the following parameters:

- o Precipitation – Mean annual precipitation over the project area is estimated to be 30 inches. The 24-hour precipitation total for a 100-year event is 5.31". Based on shed elevations, the SCS Type 1 storm pattern was used.
- o Runoff Curve Numbers – Curve numbers (CN's) reflect soil type and land use within shed areas. Soils underlying the study area are classified in the Exchequer series, in hydrologic soil group D, characterized by high runoff potential and low infiltration. CN's used in the study are summarized in Table 1.
- o Times of Concentration / Lag Times – Times of concentration for pre-project conditions were computed using standard equations. Post-project

times of concentration were assumed to be 10 – 15 minutes. Lag times were estimated to be 0.6 x time of concentration.

- Runoff Computations – The graphical HEC-1 computer program was used to develop runoff hydrographs based on the SCS unit hydrograph method.

HEC-1 hydrograph computations represent pre- and post-project runoff due to a 100-year storm. The study area encompasses only the area draining to Little Indian Creek, which was divided into on-site sheds 8, 9, 10, 11, and 12 as shown on the Exhibit. Shed W encompasses the off-site headwater area west of Highway 49. The convergence point for these sheds, the key point in the analyses, was assumed to occur where little Indian Creek crosses the north boundary of the project area.

Project build-out is assumed to result in impervious coverage of 90% of the area within Sheds 8-12. The remaining 10% of each shed is assumed to consist of landscaped area, resulting in a composite runoff curve number (CN) of 96 representing the post-project condition in each shed. Since storm drain layouts are not yet determined, times of concentration of 10 minutes or 15 minutes were assumed.

Detailed derivations of the Hec-1 input parameters, summarized in Table 1, are included in the Technical Appendix.

Table 1 – HEC-1 Input Parameters

SHED	AREA (sq mi)	PRE-PROJECT		POST-PROJECT	
		CN	LAG (hrs)	CN	LAG (hrs)
W	0.1563	74	0.255	74	0.255
8	0.0419	78	0.204	96	0.15
9	0.0578	78	0.183	96	0.15
10	0.0205	78	0.159	96	0.15
11	0.0209	80	0.124	96	0.10
12	0.0169	85	0.150	96	0.15

Detention storage for the purpose of post-project peak flow reduction is provided at the existing pond location. The goal of detention design is to limit releases so that flow at the northern project boundary, where detention outflow converges with flow in Little Indian Creek, is at or below the pre-project level. Runoff from sheds 8 and 9 is routed through the detention facility. The analyses indicate that modifications to the existing pond can result in a stage-storage-discharge configuration adequate to provide mitigation of increased runoff resulting from development within sheds 8-12. These results are summarized in Table 2. The complete HEC-1 runs are included in the Technical Appendix

Table 2 – HEC-1 Output Summary

Location	100-YEAR RUNOFF	
	<i>Pre-Project</i>	<i>Post-Project</i>
Upper reach of Little Indian Creek @ Confluence of Sheds W & 11	139 cfs	146 cfs
Middle reach of Little Indian Creek @ Confluence with Shed 10	155 cfs	177 cfs
Detention Inflow 1/	42	173 cfs
Detention Outflow 2/	41	62 cfs
Little Indian Creek @ project boundary (Confluence of detention outflow & Shed 12 with flow in main channel)	258 cfs	257 cfs

1/ Shed 8 runoff

2/ Combined runoff from Sheds 8 & 9

Hydrograph routing computations, summarized in Table 2 and included in detail in the Technical Appendix, show that increased runoff resulting from development of the Lone Band of Miwok Indians Casino Project according to assumptions outlined herein can be mitigated by means of on-site detention storage.


RESOURCES

Amador County Guidelines for Grading and Erosion Control, Amador County Public Works Agency, issued 11-21-03.

Erosion & Sediment Control Guidelines for Developing Areas of the Sierra Foothills and Mountains, High Sierra RC&D Council, October 1991.

Soil Survey Amador Area, California, United States Department of Agriculture Soil Conservation Service in cooperation with California Agricultural Experiment Station, August 1993.

TECHNICAL APPENDIX



TN / MN
15°



Map created with TOPOI® ©2002 National Geographic (www.nationalgeographic.com/topo)

SHED MAP • ONE BAND OF MINNOK INDIANS CASINO PROJECT

SCS SOIL SURVEY

AMADOR AREA, CALIFORNIA



(Joins sheet 12)

PROJECT AREA

0 1/2 1 Mile Scale 1:20,000

IONE BAND OF MIWOK INDIANS CASINO PROJECT EIS
 DERIVATION OF SHED PARAMETERS USED IN HYDROLOGIC COMPUTATIONS - PRE-PROJECT CONDITONS


SHED #	AREA (ac)	L1 (ft)	H1up (ft)	H1dwn (ft)	S1 (ft/ft)	P (in)	n	Tt1 (hr)	L2 (ft)	H2up (ft)	H2dwn (ft)	S2 (ft/ft)	V2 (ft/sec)	Tt2 (hr)	SUM T1 (hr)	LAG (hr)	CN
W	100	300	*	*	0.067	30	0.3	0.14	3200	*	*	0.025	2.55	0.35	0.42	0.255	74
1	7.6	300	1153	1065	0.293	30	0.3	0.08	900	1065	970	0.106	5.24	0.05	0.14	0.081	78
2	6.7	300	1155	1093	0.207	30	0.3	0.09	700	1093	1002	0.130	5.82	0.03	0.13	0.076	78
3	2.7	300	1154	1100	0.180	30	0.3	0.09	400	1100	1057	0.108	5.29	0.02	0.12	0.073	78
4	15.4	300	1156	1095	0.203	30	0.35	0.10	1100	1095	885	0.191	7.05	0.04	0.15	0.093	73
5	45.4	300	1062	1015	0.157	30	0.35	0.11	2000	1015	805	0.105	5.23	0.11	0.28	0.168	73
6	21.3	300	1080	1035	0.150	30	0.6	0.17	3000	1035	790	0.082	4.61	0.18	0.36	0.213	77
7	10.4	300	1110	1085	0.083	30	0.45	0.17	1000	1085	975	0.110	5.35	0.05	0.22	0.130	77.5
8	26.8	300	1078	1065	0.043	30	0.3	0.16	1200	1065	1050	0.013	1.80	0.18	0.34	0.204	78
9	37	300	1094	1079	0.050	30	0.3	0.16	2200	1079	1045	0.015	2.01	0.30	0.30	0.183	78
10	13.1	300	1099	1073	0.087	30	0.3	0.12	1100	1073	1053	0.018	2.18	0.14	0.26	0.159	78
11	13.4	300	1143	1105	0.127	30	0.3	0.11	1000	1105	1075	0.030	2.79	0.10	0.21	0.124	80
12	10.8	*	*	*	*	*	*	*	*	*	*	*	*	*	*	0.150	85

FORMULAS:


$$Tt1 = [0.007(nL)^{0.8}] / P^{0.5} S1^{0.4}$$

$$V2 = 16.1345 S2^{0.5}$$

$$Tt2 = L2 / V2 / 60$$




LEGEND

 Excluded Area

1000' — Equal Elevation

20" — Average Annual Rainfall



AVERAGE ANNUAL RAINFALL
AMADOR COUNTY RESOURCE CONSERVATION DISTRICT
 AMADOR, ALPINE AND CALAVERAS COUNTIES, CALIFORNIA

JUNE 1972

SCALE 1 : 375,000

0 2 4 6 MILES

PRECIPITATION DEPTH-DURATION-FREQUENCY TABLE

STATION NO. BSN ORDER SUB B10 4886 0
 STATION NAME LEHMAN RANCH
 ELEV 84 SEC 600 TWP 32 RNG 09N LOT 09E BWM F M LATITUDE 38.592 LONGITUDE 121.012 COUNTY CODE 09

MAXIMUM PRECIPITATION FOR INDICATED DURATION D-DAYS H-HOURS

RETURN PERIOD IN YEARS	10	20	30	40	50	60	80	100	150	200	300	600	3650
2	2.50	3.29	3.80	4.21	4.76	5.07	5.86	6.44	7.59	8.50	10.18	14.46	27.15
5	3.34	4.53	5.30	5.85	6.56	6.96	8.05	8.79	10.33	11.67	13.83	19.52	34.37
10	3.88	5.35	6.27	6.90	7.68	8.14	9.40	10.23	12.00	13.60	16.06	22.61	38.54
20	4.38	6.11	7.16	7.86	8.70	9.21	10.64	11.52	13.51	15.34	18.08	25.40	42.19
25	4.54	6.35	7.44	8.15	9.02	9.54	11.02	11.92	13.97	15.88	18.69	26.25	43.29
40	4.61	6.84	7.58	8.76	9.66	10.22	11.80	12.73	14.91	16.97	19.95	27.99	45.52
50	5.01	7.07	8.28	9.04	9.96	10.53	12.16	13.11	15.35	17.47	20.54	28.86	46.54
100	5.46	7.77	9.10	9.90	10.86	11.48	13.26	14.24	16.66	18.99	22.29	31.23	49.57
200	5.91	8.46	9.89	10.74	11.73	12.40	14.31	15.32	17.93	20.45	23.98	33.57	52.45
1000	6.91	10.00	11.67	12.60	13.67	14.43	16.66	17.72	20.73	23.68	27.71	38.74	58.68
10000	8.28	12.14	14.12	15.15	16.31	17.20	19.86	20.96	24.50	28.04	32.75	45.71	66.87
PMP	16.28	23.64	28.41	31.31	34.53	36.34	41.93	45.45	53.02	60.99	70.80	98.39	149.29
MEAN	2.662	3.552	4.094	4.501	5.051	5.375	6.217	6.783	7.985	8.962	10.711	15.195	27.826
CLOCK HR. COR.	1.140	1.070	1.040	1.020	1.010	1.010	1.000	1.000	1.000	1.000	1.000	1.000	1.000
CALCULATED SKEW	1.660	2.340	1.622	1.591	1.309	1.200	1.007	1.069	.695	.930	1.275	1.033	.464
REGIONAL SKEW	1.100	1.200	1.100	1.000	.900	.900	.900	.800	.800	.800	.800	.800	.500
SKEW USED	1.100	1.200	1.100	1.000	.900	.900	.900	.800	.800	.800	.800	.800	.500
KURTOSIS	6.625	9.318	5.837	5.854	5.150	4.963	4.593	4.881	3.397	3.814	4.846	3.818	2.240
N	24	24	24	24	24	24	24	24	24	24	24	24	24
RECORD YEAR	1956	1956	1956	1956	1956	1956	1956	1956	1956	1956	1956	1956	1956
RECORD MAXIMUM	5.000	8.500	8.750	10.450	11.550	12.150	13.350	14.950	16.050	18.200	23.240	28.540	44.870
NORMALIZED MAX	2.489	3.155	2.672	2.878	2.888	2.871	2.873	2.954	2.516	2.568	2.887	2.473	2.025
CALC. COEF. VAR	.353	.442	.426	.459	.446	.439	.399	.408	.401	.401	.405	.355	.302
REGN. COEF. VAR	.341	.377	.396	.397	.389	.384	.383	.380	.376	.387	.374	.365	.291
USED COEF. VAR	.341	.377	.396	.397	.389	.384	.383	.380	.376	.387	.374	.365	.291
MEAN/A	.0957	.1277	.1471	.1618	.1815	.1932	.2234	.2438	.2870	.3221	.3849	.5461	1.0000
RP10/A	.1394	.1922	.2253	.2478	.2761	.2925	.3380	.3676	.4312	.4887	.5773	.8125	1.3850
RP25/A	.1631	.2281	.2675	.2929	.3241	.3429	.3961	.4284	.5020	.5705	.6719	.9434	1.5559
RP50/A	.1800	.2541	.2977	.3250	.3579	.3785	.4372	.4710	.5516	.6279	.7381	1.0350	1.6725
RP100/A	.1964	.2792	.3270	.3559	.3904	.4126	.4765	.5116	.5989	.6825	.8011	1.1223	1.7815
RP1000/A	.2482	.3594	.4194	.4527	.4914	.5187	.5989	.6370	.7449	.8512	.9960	1.3921	2.1090
RP10000/A	.2975	.4363	.5075	.5443	.5861	.6182	.7136	.7534	.8805	1.0078	1.1769	1.6426	2.4030
PMP/A	.5851	.8496	1.0211	1.1251	1.2408	1.3059	1.5069	1.6333	1.9054	2.1918	2.5443	3.5359	5.3650

PRECIPITATION DEPTH-DURATION-FREQUENCY TABLE

STATION NO. BSN ORDER SUB B10 7000 0
 STATION NAME PLYMOUTH
 ELEV 1096 SEC 11 TWP 07N RING LOT 10E BWM C M LATITUDE 38.483 LONGITUDE 120.845 COUNTY CODE 03

MAXIMUM PRECIPITATION FOR INDICATED DURATION D-DAYS H-HOURS

RETURN PERIOD IN YEARS	10	20	30	40	50	60	80	100	200	300	600	F YR
2	2.43	3.28	3.86	4.30	4.77	5.18	5.79	6.16	8.22	10.06	14.86	27.54
5	3.24	4.52	5.38	5.98	6.58	7.12	7.95	8.40	11.27	13.66	20.06	35.15
10	3.77	5.33	6.36	7.05	7.70	8.32	9.29	9.77	13.14	15.86	23.23	39.78
20	4.25	6.09	7.27	8.03	8.73	9.42	10.51	11.01	14.82	17.85	26.09	43.98
25	4.41	6.33	7.55	8.33	9.04	9.76	10.88	11.39	15.34	18.46	26.97	45.26
40	4.48	6.82	7.69	8.95	9.69	10.45	11.65	12.16	16.39	19.71	28.76	47.88
50	4.86	7.05	8.41	9.24	9.99	10.77	12.01	12.52	16.88	20.28	29.59	49.09
100	5.31	7.75	9.23	10.12	10.89	11.74	13.09	13.60	18.35	22.01	32.09	52.74
200	5.74	8.43	10.04	10.97	11.77	12.68	14.13	14.64	19.76	23.68	34.49	56.26
1000	6.70	9.97	11.84	12.87	13.71	14.76	16.45	16.93	22.89	27.37	39.80	64.02
10000	8.04	12.10	14.33	15.48	16.35	17.59	19.61	20.03	27.10	32.34	46.96	74.50
PMP	15.81	23.57	28.83	31.99	34.62	37.16	41.40	43.42	58.93	69.92	101.09	153.68
MEAN	2.585	3.542	4.155	4.599	5.066	5.497	6.138	6.480	8.660	10.577	15.612	28.645
CLOCK HR. COR.	1.140	1.070	1.050	1.040	1.030	1.020	1.020	1.010	1.010	1.000	1.000	1.000
CALCULATED SKEW	1.576	1.169	1.335	1.362	.982	.729	.707	.776	.758	.665	.480	.134
REGIONAL SKEW	1.100	1.200	1.100	1.000	.900	.900	.900	.800	.800	.800	.800	.800
SKEW USED	1.100	1.200	1.100	1.000	.900	.900	.900	.800	.800	.800	.800	.800
KURTOSIS	6.012	4.072	4.911	5.371	4.171	3.186	3.130	3.341	2.745	2.792	2.489	2.212
N	25	25	25	25	25	25	25	25	25	25	25	25
RECORD YEAR	1945	1951	1951	1951	1951	1951	1951	1951	1956	1956	1936	1958
RECORD MAXIMUM	4.090	6.070	7.870	9.770	10.110	10.270	10.810	11.210	15.180	18.320	25.190	40.790
NORMALIZED MAX	1.972	2.284	2.431	2.800	2.559	2.242	2.153	2.093	1.966	2.000	1.922	1.673
CALC. COEF. VAR	.295	.313	.368	.401	.389	.387	.354	.349	.383	.366	.319	.253
REGN. COEF. VAR	.341	.377	.396	.397	.389	.384	.383	.380	.387	.374	.365	.291
USED COEF. VAR	.341	.377	.396	.397	.389	.384	.383	.380	.387	.374	.365	.291
MEAN/A	.0902	.1236	.1450	.1606	.1768	.1919	.2143	.2262	.3023	.3693	.5450	1.0000
RP10/A	.1315	.1861	.2221	.2460	.2689	.2906	.3242	.3411	.4587	.5538	.8109	1.3889
RP25/A	.1538	.2210	.2637	.2908	.3157	.3407	.3800	.3976	.5355	.6445	.9415	1.5800
RP50/A	.1698	.2461	.2935	.3226	.3487	.3760	.4193	.4371	.5893	.7080	1.0330	1.7138
RP100/A	.1852	.2704	.3223	.3532	.3803	.4099	.4570	.4748	.6406	.7685	1.1201	1.8413
RP1000/A	.2341	.3481	.4135	.4494	.4787	.5153	.5744	.5911	.7989	.9554	1.3894	2.2351
RP10000/A	.2806	.4225	.5003	.5403	.5709	.6141	.6845	.6991	.9460	1.1290	1.6394	2.6009
PMP/A	.5519	.8228	1.0066	1.1167	1.2087	1.2974	1.4454	1.5157	2.0573	2.4408	3.5290	5.3650

PEARSON TYPE III DISTRIBUTION USED
 PROBABLE MAXIMUM PRECIPITATION ESTIMATE BASED ON 15 STANDARD DEVIATIONS
 WHERE N IS SMALL RESULTS ARE NOT DEPENDABLE

PRE-PROJECT

HEC1 S/N: 1343001909

HMVersion: 6.33

C:\HAESTAD\GHEC1\SAMPLE\PLYMPRE.OUT
Data File: C:\WINDOWS\TEMP\vbh0C5B.TMP

```

*****
* FLOOD HYDROGRAPH PACKAGE (HEC-1) *
*   MAY 1991 *
*   VERSION 4.0.1E *
* RUN DATE 01/17/2004 TIME 20:18:34 *
*****
    
```

```

*****
* U.S. ARMY CORPS OF ENGINEERS *
* HYDROLOGIC ENGINEERING CENTER *
* 609 SECOND STREET *
* DAVIS, CALIFORNIA 95616 *
* (916) 756-1104 *
*****
    
```

```

X X XXXXXX XXXXX X
X X X X X XX
X X X X X X
XXXXXX XXXX X XXXXX X
X X X X X X
X X X X X X
X X XXXXXX XXXXX XXX
    
```

```

*****
Full Microcomputer Implementation
by
Haestad Methods, Inc.
*****
    
```

37 Brookside Road * Waterbury, Connecticut 06708 * (203) 755-1666

THIS PROGRAM REPLACES ALL PREVIOUS VERSIONS OF HEC-1 KNOWN AS HEC1 (JAN 73), HEC1GS, HEC1DB, AND HEC1KW.

THE DEFINITIONS OF VARIABLES -RTIMP- AND -RTIOR- HAVE CHANGED FROM THOSE USED WITH THE 1973-STYLE INPUT STRUCTURE. THE DEFINITION OF -ANSEK- ON RM-CARD WAS CHANGED WITH REVISIONS DATED 28 SEP 81. THIS IS THE FORTRAN77 VERSION. NEW OPTIONS: DAMBREAK OUTFLOW SUBMERGENCE, SINGLE EVENT DAMAGE CALCULATION, DSS-WRITE STAGE FREQUENCY, DSS-READ TIME SERIES AT DESIRED CALCULATION INTERVAL, LOSS RATE:GREEN AND AMPT INFILTRATION. KINEMATIC WAVE: NEW FINITE DIFFERENCE ALGORITHM.

HEC-1 INPUT		PAGE 1									
LINE	ID.....1.....2.....3.....4.....5.....6.....7.....8.....9.....10										
1	ID 100-YEAR PRE-PROJECT RUNOFF FOR NORTH AREA										
2	IT 5 310										
3	IO 5 0										
4	KK SHED W										
5	KM OFFSITE AREA, W. OF HWY 49										
6	KO 22										
7	BA 0.1563										
8	PB 5.31										
9	IN 6										
10	PC 0.0000 0.00174 0.00348 0.00522 0.00697 0.00871 0.01046 0.01220 0.01395 0.01570										
11	PC 0.0174 0.01920 0.02095 0.02270 0.02446 0.02621 0.02797 0.02972 0.03148 0.03324										
12	PC 0.0350 0.03677 0.03858 0.04041 0.04227 0.04416 0.04608 0.04803 0.05001 0.05201										
13	PC 0.0540 0.05611 0.05821 0.06033 0.06248 0.06466 0.06687 0.06911 0.07138 0.07367										
14	PC 0.0760 0.07835 0.08070 0.08307 0.08545 0.08784 0.09024 0.09265 0.09507 0.09751										
15	PC 0.1000 0.10241 0.10487 0.10735 0.10984 0.11234 0.11485 0.11737 0.11990 0.12245										
16	PC 0.1250 0.12761 0.13034 0.13317 0.13610 0.13915 0.14230 0.14557 0.14894 0.15241										
17	PC 0.1560 0.15966 0.16334 0.16706 0.17082 0.17460 0.17842 0.18226 0.18614 0.19006										
18	PC 0.1940 0.19817 0.20275 0.20775 0.21317 0.21900 0.22523 0.23185 0.23885 0.24623										
19	PC 0.2540 0.26233 0.27139 0.28119 0.29173 0.30300 0.31942 0.34542 0.38784 0.46316										

C:\HAESTAD\GHEC1\SAMPLE\PLYMPRE.OUT

20	PC	0.5150	0.53220	0.54760	0.56120	0.57300	0.58300	0.59188	0.60032	0.60832	0.61588
21	PC	0.6230	0.62982	0.63648	0.64298	0.64932	0.65550	0.66152	0.66738	0.67308	0.67862
22	PC	0.6840	0.68925	0.69440	0.69945	0.70440	0.70925	0.71400	0.71865	0.72320	0.72765
23	PC	0.7320	0.73625	0.74040	0.74445	0.74840	0.75225	0.75600	0.75965	0.76320	0.76665
24	PC	0.7700	0.77329	0.77656	0.77981	0.78304	0.78625	0.78944	0.79261	0.79576	0.79889
25	PC	0.8020	0.80509	0.80816	0.81121	0.81424	0.81725	0.82024	0.82321	0.82616	0.82909
26	PC	0.8320	0.83489	0.83776	0.84061	0.84344	0.84625	0.84904	0.85181	0.85456	0.85729
27	PC	0.8600	0.86269	0.86536	0.86801	0.87064	0.87325	0.87584	0.87841	0.88096	0.88349
28	PC	0.8860	0.88849	0.89096	0.89341	0.89584	0.89825	0.90064	0.90301	0.90536	0.90769
29	PC	0.9100	0.91229	0.91456	0.91681	0.91904	0.92125	0.92344	0.92561	0.92776	0.92989
30	PC	0.9320	0.93409	0.93616	0.93821	0.94024	0.94225	0.94424	0.94621	0.94816	0.95009
31	PC	0.9520	0.95389	0.95576	0.95761	0.95944	0.96125	0.96304	0.96481	0.96656	0.96829
32	PC	0.9700	0.97169	0.97336	0.97501	0.97664	0.97825	0.97984	0.98141	0.98296	0.98449
33	PC	0.9860	0.98749	0.98896	0.99041	0.99184	0.99325	0.99464	0.99601	0.99736	0.99869
34	PC	1.0000	1.00000	1.00000	1.00000	1.00000					

35 LS 74
36 UD 0.255

37 KK SHED11
38 KM
39 KO 22
40 BA .0209
41 LS 80
42 UD 0.124

43 KK SUM1
44 KM
45 KO 22
46 HC 2

HRC-1 INPUT

LINE ID.....1.....2.....3.....4.....5.....6.....7.....8.....9.....10

47 KK RTE1
48 KM ESTIMATED SECTION
49 KO 22
50 RD 1400 .01 .035 TRAP 5 3

51 KK SHED10
52 KM
53 KO 22
54 BA .0205
55 LS 78
56 UD 0.159

57 KK SUM2
58 KM
59 KO 22
60 HC 2

61 KK RTE2
62 KM ESTIMATED SECTION
63 KO 22
64 RD 1100 .008 .035 TRAP 5 3

65 KK SHED8
66 KM
67 KO 22
68 BA .0419
69 LS 78
70 UD .204

71 KK POND1
72 KM ROUTE THROUGH EX. ON-SITE POND
73 KO 22
74 RS 1 ELEV 1047.7
75 SA .063 0.33 0.58
76 SE 1047.7 1050 1051
77 SL 1045 .01 0.6 0.5
78 SS 1050.5 125 3 1.5

79 KK SHED 9
80 KM
81 KO 22
82 BA .0578
83 LS 78

84 UD 0.183
85 KK SHED12
86 KM
87 KO 22
88 BA .0169
89 LS 85
90 UD .15

HEC-1 INPUT

PAGE 3

LINE ID.....1.....2.....3.....4.....5.....6.....7.....8.....9.....10

91 KK BNDY
92 KM COMBINED RUNOFF @ APPROX. PROJECT BOUNDARY
93 KO 22
94 HC 4
95 ZZ

HEC1 S/N: 1343001909 HMVersion: 6.33 Data File:
C:\WINDOWS\TEMP\vbh0C5B.TMP

* FLOOD HYDROGRAPH PACKAGE (HEC-1) *
* MAY 1991 *
* VERSION 4.0.1E *
* RUN DATE 01/17/2004 TIME 20:18:34 *

* U.S. ARMY CORPS OF ENGINEERS *
* HYDROLOGIC ENGINEERING CENTER *
* 609 SECOND STREET *
* DAVIS, CALIFORNIA 95616 *
* (916) 756-1104 *

100-YEAR PRE-PROJECT RUNOFF FOR NORTH AREA

3 IO OUTPUT CONTROL VARIABLES

IPRNT 5 PRINT CONTROL
IPLOT 0 PLOT CONTROL
QSCAL 0. HYDROGRAPH PLOT SCALE

IT HYDROGRAPH TIME DATA

NMIN 5 MINUTES IN COMPUTATION INTERVAL
IDATE 1 0 STARTING DATE
ITIME 0000 STARTING TIME
NQ 310 NUMBER OF HYDROGRAPH ORDINATES
NDDATE 2 0 ENDING DATE
NDTIME 0145 ENDING TIME
ICENT 19 CENTURY MARK

COMPUTATION INTERVAL 0.08 HOURS
TOTAL TIME BASE 25.75 HOURS

ENGLISH UNITS

DRAINAGE AREA SQUARE MILES
PRECIPITATION DEPTH INCHES
LENGTH, ELEVATION FEET
FLOW CUBIC FEET PER SECOND
STORAGE VOLUME ACRE-Feet
SURFACE AREA ACRES
TEMPERATURE DEGREES FAHRENHEIT

4 KK
* SHED W *

6 KO OUTPUT CONTROL VARIABLES

IPRNT 5 PRINT CONTROL
IPLOT 0 PLOT CONTROL

QSCAL	0.	HYDROGRAPH PLOT SCALE
IPNCH	0	PUNCH COMPUTED HYDROGRAPH
IOUT	22	SAVE HYDROGRAPH ON THIS UNIT
ISAV1	1	FIRST ORDINATE PUNCHED OR SAVED
ISAV2	310	LAST ORDINATE PUNCHED OR SAVED
TIMINT	0.083	TIME INTERVAL IN HOURS

.....

```
*****
*   *
* SHED11 *
*   *
*****
```

39 KO OUTPUT CONTROL VARIABLES

IPRNT	5	PRINT CONTROL
IPLOT	0	PLOT CONTROL
QSCAL	0.	HYDROGRAPH PLOT SCALE
IPNCH	0	PUNCH COMPUTED HYDROGRAPH
IOUT	22	SAVE HYDROGRAPH ON THIS UNIT
ISAV1	1	FIRST ORDINATE PUNCHED OR SAVED
ISAV2	310	LAST ORDINATE PUNCHED OR SAVED
TIMINT	0.083	TIME INTERVAL IN HOURS

.....

```
*****
*   *
* SUM1 *
*   *
*****
```

45 KO OUTPUT CONTROL VARIABLES

IPRNT	5	PRINT CONTROL
IPLOT	0	PLOT CONTROL
QSCAL	0.	HYDROGRAPH PLOT SCALE
IPNCH	0	PUNCH COMPUTED HYDROGRAPH
IOUT	22	SAVE HYDROGRAPH ON THIS UNIT
ISAV1	1	FIRST ORDINATE PUNCHED OR SAVED
ISAV2	310	LAST ORDINATE PUNCHED OR SAVED
TIMINT	0.083	TIME INTERVAL IN HOURS

.....

```
*****
*   *
* RTE1 *
*   *
*****
```

49 KO OUTPUT CONTROL VARIABLES

IPRNT	5	PRINT CONTROL
IPLOT	0	PLOT CONTROL
QSCAL	0.	HYDROGRAPH PLOT SCALE
IPNCH	0	PUNCH COMPUTED HYDROGRAPH
IOUT	22	SAVE HYDROGRAPH ON THIS UNIT
ISAV1	1	FIRST ORDINATE PUNCHED OR SAVED
ISAV2	310	LAST ORDINATE PUNCHED OR SAVED
TIMINT	0.083	TIME INTERVAL IN HOURS

51 KK

```
*****
*   SHED10   *
*****
```

53 KO

OUTPUT CONTROL VARIABLES

IPRNT	5	PRINT CONTROL
IPLOT	0	PLOT CONTROL
QSCAL	0.	HYDROGRAPH PLOT SCALE
IPNCH	0	PUNCH COMPUTED HYDROGRAPH
IOUT	22	SAVE HYDROGRAPH ON THIS UNIT
ISAV1	1	FIRST ORDINATE PUNCHED OR SAVED
ISAV2	310	LAST ORDINATE PUNCHED OR SAVED
TIMINT	0.083	TIME INTERVAL IN HOURS

57 KK

```
*****
*   SUM2     *
*****
```

59 KO

OUTPUT CONTROL VARIABLES

IPRNT	5	PRINT CONTROL
IPLOT	0	PLOT CONTROL
QSCAL	0.	HYDROGRAPH PLOT SCALE
IPNCH	0	PUNCH COMPUTED HYDROGRAPH
IOUT	22	SAVE HYDROGRAPH ON THIS UNIT
ISAV1	1	FIRST ORDINATE PUNCHED OR SAVED
ISAV2	310	LAST ORDINATE PUNCHED OR SAVED
TIMINT	0.083	TIME INTERVAL IN HOURS

61 KK

```
*****
*   RTE2     *
*****
```

63 KO

OUTPUT CONTROL VARIABLES

IPRNT	5	PRINT CONTROL
IPLOT	0	PLOT CONTROL
QSCAL	0.	HYDROGRAPH PLOT SCALE
IPNCH	0	PUNCH COMPUTED HYDROGRAPH
IOUT	22	SAVE HYDROGRAPH ON THIS UNIT
ISAV1	1	FIRST ORDINATE PUNCHED OR SAVED
ISAV2	310	LAST ORDINATE PUNCHED OR SAVED
TIMINT	0.083	TIME INTERVAL IN HOURS

65 KK

```
*****
*   SHED8    *
*****
```

67 KO

OUTPUT CONTROL VARIABLES

```
IPRNT      5  PRINT CONTROL
IPLOT      0  PLOT CONTROL
QSCAL     0.  HYDROGRAPH PLOT SCALE
IPNCH      0  PUNCH COMPUTED HYDROGRAPH
IOUT      22  SAVE HYDROGRAPH ON THIS UNIT
ISAV1      1  FIRST ORDINATE PUNCHED OR SAVED
ISAV2     310 LAST ORDINATE PUNCHED OR SAVED
TIMINT    0.083 TIME INTERVAL IN HOURS
```

```
*****
*          *
71 KK  * POND1 *
*          *
*****
```

```
73 KO      OUTPUT CONTROL VARIABLES
IPRNT      5  PRINT CONTROL
IPLOT      0  PLOT CONTROL
QSCAL     0.  HYDROGRAPH PLOT SCALE
IPNCH      0  PUNCH COMPUTED HYDROGRAPH
IOUT      22  SAVE HYDROGRAPH ON THIS UNIT
ISAV1      1  FIRST ORDINATE PUNCHED OR SAVED
ISAV2     310 LAST ORDINATE PUNCHED OR SAVED
TIMINT    0.083 TIME INTERVAL IN HOURS
```

```
*****
*          *
79 KK  * SHED 9 *
*          *
*****
```

```
81 KO      OUTPUT CONTROL VARIABLES
IPRNT      5  PRINT CONTROL
IPLOT      0  PLOT CONTROL
QSCAL     0.  HYDROGRAPH PLOT SCALE
IPNCH      0  PUNCH COMPUTED HYDROGRAPH
IOUT      22  SAVE HYDROGRAPH ON THIS UNIT
ISAV1      1  FIRST ORDINATE PUNCHED OR SAVED
ISAV2     310 LAST ORDINATE PUNCHED OR SAVED
TIMINT    0.083 TIME INTERVAL IN HOURS
```

```
*****
*          *
85 KK  * SHED12 *
*          *
*****
```

```
87 KO      OUTPUT CONTROL VARIABLES
IPRNT      5  PRINT CONTROL
IPLOT      0  PLOT CONTROL
QSCAL     0.  HYDROGRAPH PLOT SCALE
IPNCH      0  PUNCH COMPUTED HYDROGRAPH
IOUT      22  SAVE HYDROGRAPH ON THIS UNIT
ISAV1      1  FIRST ORDINATE PUNCHED OR SAVED
ISAV2     310 LAST ORDINATE PUNCHED OR SAVED
TIMINT    0.083 TIME INTERVAL IN HOURS
```

91 KK *****
 * BNDY *

93 KO OUTPUT CONTROL VARIABLES
 IPRNT 5 PRINT CONTROL
 IPLOT 0 PLOT CONTROL
 QSCAL 0 HYDROGRAPH PLOT SCALE
 IPNCH 0 PUNCH COMPUTED HYDROGRAPH
 IOUT 22 SAVE HYDROGRAPH ON THIS UNIT
 ISAV1 1 FIRST ORDINATE PUNCHED OR SAVED
 ISAV2 310 LAST ORDINATE PUNCHED OR SAVED
 TIMINT 0.083 TIME INTERVAL IN HOURS

RUNOFF SUMMARY
 FLOW IN CUBIC FEET PER SECOND
 TIME IN HOURS, AREA IN SQUARE MILES

OPERATION	STATION	PEAK FLOW	TIME OF PEAK 6-HOUR	AVERAGE FLOW FOR MAXIMUM PERIOD			BASIN AREA	MAXIMUM STAGE	TIME OF MAX STAGE
24-HOUR	72-HOUR								
HYDROGRAPH AT SHED W	120.	10.17	28.	11.	10.	0.16			
HYDROGRAPH AT SHED11	26.	10.00	5.	2.	2.	0.02			
2 COMBINED AT SUM1	139.	10.08	33.	13.	12.	0.18			
ROUTED TO RTE1	137.	10.17	33.	13.	12.	0.18			
HYDROGRAPH AT SHED10	22.	10.08	4.	2.	2.	0.02			
2 COMBINED AT SUM2	155.	10.17	37.	14.	13.	0.20			
ROUTED TO RTE2	150.	10.25	37.	14.	13.	0.20			
HYDROGRAPH AT SHED8	42.	10.08	9.	3.	3.	0.04			
ROUTED TO PCND1	41.	10.08	8.	3.	3.	0.04			
1050.73	10.08								
HYDROGRAPH AT SHED 9	60.	10.08	12.	5.	4.	0.06			
HYDROGRAPH AT SHED12	23.	10.00	4.	2.	2.	0.02			
4 COMBINED AT BNDY	258.	10.17	61.	24.	22.				
0.31									

SUMMARY OF KINEMATIC WAVE - MUSKINGUM-CUNGE ROUTING
 (FLOW IS DIRECT RUNOFF WITHOUT BASE FLOW)

ISTAQ	ELEMENT	DT	PEAK	TIME TO PEAK	VOLUME	DT	INTERPOLATED TO COMPUTATION INTERVAL		VOLUME
							PEAK	TIME TO PEAK	
		(MIN)	(CFS)	(MIN)	(IN)	(MIN)	(CFS)	(MIN)	(IN)
RTE1	MANE	4.02	138.35	610.45	2.68	5.00	137.43	610.00	2.68

CONTINUITY SUMMARY (AC-FT) - INFLOW=0.2531E+02 EXCESS=0.0000E+00 OUTFLOW=0.2532E+02 BASIN STORAGE=0.8775E-03 PERCENT ERROR= 0.0

RTE2	MANE	3.32	151.57	611.07	2.71	5.00	150.27	615.00	2.71
------	------	------	--------	--------	------	------	--------	--------	------

CONTINUITY SUMMARY (AC-FT) - INFLOW=0.2857E+02 EXCESS=0.0000E+00 OUTFLOW=0.2857E+02 BASIN STORAGE=0.9837E-03 PERCENT ERROR= 0.0

C:\HAESTAD\GHECI\SAMPLE\PLYMPRE.OUT

*** NORMAL END OF HEC-1 ***

POST. PROJECT

HEC1 S/N: 1343001909 HWVersion: 6.33 Data File: C:\HAESTAD\GHEC1\SAMPLE\FLYMPST.OUT
 C:\HAESTAD\GHEC1\SAMPLE\FLYMPST.OUT
 C:\WINDOWS\TEMP\~vbn106F.TMP

```
*****
* FLOOD HYDROGRAPH PACKAGE (HEC-1) *
* MAY 1991 *
* VERSION 4.0.18 *
* RUN DATE 01/24/2004 TIME 15:55:35 *
*****
```

```
*****
* U.S. ARMY CORPS OF ENGINEERS *
* HYDROLOGIC ENGINEERING CENTER *
* 609 SECOND STREET *
* DAVIS, CALIFORNIA 95616 *
* (916) 756-1104 *
*****
```

```

X   X  XXXXXX  XXXX   X
X   X  X      X   X   XX
X   X  X      X   X   X
XXXXXXX XXXX  X     XXXXX X
X   X  X      X   X   X
X   X  X      X   X   X
X   X  XXXXXX  XXXXX  XXX

```

```

.....
.....
... Full Microcomputer Implementation ...
... by ...
... Haestad Methods, Inc. ...
...
.....
.....

```

37 Brookside Road * Waterbury, Connecticut 06708 * (203) 755-1666

THIS PROGRAM REPLACES ALL PREVIOUS VERSIONS OF HEC-1 KNOWN AS HEC1 (JAN 73), HEC1G5, HEC1DB, AND HEC1KW.
 THE DEFINITIONS OF VARIABLES -RTIMP- AND -RTIOR- HAVE CHANGED FROM THOSE USED WITH THE 1973-STYLE INPUT STRUCTURE.
 THE DEFINITION OF -AMSKK- ON RM-CARD WAS CHANGED WITH REVISIONS DATED 28 SEP 81. THIS IS THE FORTRAN77 VERSION
 NEW OPTIONS: DAMBREAK OUTFLOW SUBMERGENCE, SINGLE EVENT DAMAGE CALCULATION, DSS:WRITE STAGE FREQUENCY,
 DSS:READ TIME SERIES AT DESIRED CALCULATION INTERVAL LOSS RATE:GREEN AND AMPT INFILTRATION
 KINEMATIC WAVE: NEW FINITE DIFFERENCE ALGORITHM

HEC-1 INPUT		PAGE 1									
LINE	ID.....1.....2.....3.....4.....5.....6.....7.....8.....9.....10										
1	ID	100-YEAR POST-PROJECT RUNOFF (NORTH AREA)									
2	IT	5	310								
3	IO	5	0								
4	KK	SHED W									
5	KM	OPPOSITE AREA, W. OF HWY 49									
6	KO		22								
7	KA	0.1563									
8	PB	5.31									
9	IN	6									
10	PC	0.0000	0.00174	0.00348	0.00522	0.00697	0.00871	0.01046	0.01220	0.01395	0.01570
11	PC	0.0174	0.01920	0.02095	0.02270	0.02446	0.02621	0.02797	0.02972	0.03148	0.03324
12	PC	0.0350	0.03677	0.03858	0.04041	0.04227	0.04416	0.04608	0.04803	0.05001	0.05201
13	PC	0.0540	0.05611	0.05821	0.06033	0.06248	0.06466	0.06687	0.06911	0.07138	0.07367
14	PC	0.0760	0.07835	0.08070	0.08307	0.08545	0.08784	0.09024	0.09265	0.09507	0.09751
15	PC	0.1000	0.10241	0.10487	0.10735	0.10984	0.11234	0.11485	0.11737	0.11990	0.12245
16	PC	0.1250	0.12761	0.13034	0.13317	0.13610	0.13915	0.14230	0.14557	0.14894	0.15241
17	PC	0.1560	0.15966	0.16334	0.16706	0.17082	0.17460	0.17842	0.18226	0.18614	0.19006
18	PC	0.1940	0.19817	0.20275	0.20775	0.21317	0.21900	0.22523	0.23185	0.23885	0.24623
19	PC	0.2540	0.26233	0.27139	0.28119	0.29173	0.30300	0.31492	0.34542	0.38784	0.46316

C:\HAESTAD\GHEC1\SAMPLE\FLYMPST.OUT

20	PC	0.5150	0.53220	0.54760	0.56120	0.57300	0.58300	0.59188	0.60032	0.60832	0.61588
21	PC	0.6230	0.62982	0.63648	0.64298	0.64932	0.65550	0.66152	0.66738	0.67308	0.67862
22	PC	0.6840	0.68925	0.69440	0.69945	0.70440	0.70925	0.71400	0.71865	0.72320	0.72765
23	PC	0.7320	0.73625	0.74040	0.74445	0.74840	0.75225	0.75600	0.75965	0.76320	0.76665
24	PC	0.7700	0.77329	0.77656	0.77981	0.78304	0.78625	0.78944	0.79261	0.79576	0.79889
25	PC	0.8020	0.80509	0.80816	0.81121	0.81424	0.81725	0.82024	0.82321	0.82616	0.82909
26	PC	0.8320	0.83489	0.83776	0.84061	0.84344	0.84625	0.84904	0.85181	0.85456	0.85729
27	PC	0.8600	0.86269	0.86536	0.86801	0.87064	0.87325	0.87584	0.87841	0.88096	0.88349
28	PC	0.8860	0.88849	0.89096	0.89341	0.89584	0.89825	0.90064	0.90301	0.90536	0.90769
29	PC	0.9100	0.91229	0.91456	0.91681	0.91904	0.92125	0.92344	0.92561	0.92776	0.92989
30	PC	0.9320	0.93409	0.93616	0.93821	0.94024	0.94225	0.94424	0.94621	0.94816	0.95009
31	PC	0.9520	0.95389	0.95576	0.95761	0.95944	0.96125	0.96304	0.96481	0.96656	0.96829
32	PC	0.9700	0.97169	0.97336	0.97501	0.97664	0.97825	0.97984	0.98141	0.98296	0.98449
33	PC	0.9860	0.98749	0.98896	0.99041	0.99184	0.99325	0.99464	0.99601	0.99736	0.99869
34	PC	1.0000	1.00000	1.00000	1.00000	1.00000	1.00000	1.00000	1.00000	1.00000	1.00000
35	LS		74								
36	UD	0.255									

37	KK	SHED11									
38	KM	POST-PROJECT; ASSUME 90% IMPERVIOUS; 10 MIN. TIME OF CONCENTRATION									
39	KO						22				
40	BA	.0209									
41	LS		96								
42	UD	0.1									
43	KK	SUM1									
44	KM										
45	KO						22				
46	HC	2									

HEC-1 INPUT

PAGE 2

LINE ID.....1.....2.....3.....4.....5.....6.....7.....8.....9.....10

47	KK	RTE1									
48	KM	ESTIMATED SECTION									
49	KO						22				
50	RD	1400	.01	.035		TRAP	5	3			
51	KK	SHED10									
52	KM	POST-PROJECT; ASSUME 90% IMPERVIOUS; 10 MIN. TIME OF CONCENTRATION									
53	KO						22				
54	BA	.0205									
55	LS		96								
56	UD	0.1									
57	KK	SUM2									
58	KM										
59	KO						22				
60	HC	2									
61	KK	RTE2									
62	KM	ESTIMATED SECTION									
63	KO						22				
64	RD	1100	.008	.035		TRAP	5	3			
65	KK	SHED8									
66	KM	POST-PROJECT; ASSUME 90% IMPERVIOUS; 15 MIN. TIME OF CONCENTRATION									
67	KO						22				
68	BA	.0419									
69	LS		96								
70	UD	.15									
71	KK	SHED 9									
72	KM	POST-PROJECT; ASSUME 90% IMPERVIOUS; 15 MIN. TIME OF CONCENTRATION									
73	KO						22				
74	BA	.0578									
75	LS		96								
76	UD	0.15									
77	KK	SHED12									
78	KM	POST-PROJECT; ASSUME 90% IMPERVIOUS; 15 MIN. TIME OF CONCENTRATION									
79	KO						22				
80	BA	.0169									
81	LS		96								
82	UD	.15									

83 KK BNDY
84 KM COMBINED RUNOFF @ APPROX. PROJECT BOUNDARY
85 KO 22
86 HC 4
87 EE

.HEC1 S/N: 1343001909 HMVersion: 6.33 Data File:
C:\WINDOWS\TEMP\vbh106F.TMP

* FLOOD HYDROGRAPH PACKAGE (HEC-1) *
* MAY 1991 *
* VERSION 4.0.1E *
* RUN DATE 01/24/2004 TIME 15:55:35 *

* U.S. ARMY CORPS OF ENGINEERS *
* HYDROLOGIC ENGINEERING CENTER *
* 609 SECOND STREET *
* DAVIS, CALIFORNIA 95616 *
* (916) 756-1104 *

100-YEAR POST-PROJECT RUNOFF (NORTH AREA)

3 IO OUTPUT CONTROL VARIABLES
IPRNT 5 PRINT CONTROL
IPLOT 0 PLOT CONTROL
QSCAL 0. HYDROGRAPH PLOT SCALE

IT HYDROGRAPH TIME DATA
MMIN 5 MINUTES IN COMPUTATION INTERVAL
IDATE 1 0 STARTING DATE
ITIME 0000 STARTING TIME
NQ 310 NUMBER OF HYDROGRAPH ORDINATES
NDDATE 2 0 ENDING DATE
NDTIME 0145 ENDING TIME
ICENT 19 CENTURY MARK

COMPUTATION INTERVAL 0.08 HOURS
TOTAL TIME BASE 25.75 HOURS

ENGLISH UNITS
DRAINAGE AREA SQUARE MILES
PRECIPITATION DEPTH INCHES
LENGTH, ELEVATION FEET
FLOW CUBIC FEET PER SECOND
STORAGE VOLUME ACRE-Feet
SURFACE AREA ACRES
TEMPERATURE DEGREES FAHRENHEIT

* SHED W *

6 KO OUTPUT CONTROL VARIABLES
IPRNT 5 PRINT CONTROL
IPLOT 0 PLOT CONTROL
QSCAL 0. HYDROGRAPH PLOT SCALE
IPNCH 0 PUNCH COMPUTED HYDROGRAPH
ICUT 22 SAVE HYDROGRAPH ON THIS UNIT
ISAV1 1 FIRST ORDINATE PUNCHED OR SAVED
ISAV2 310 LAST ORDINATE PUNCHED OR SAVED
TIMINT 0.083 TIME INTERVAL IN HOURS

```
*****  
*      *  
37 KK  *  SHED11  *  
*      *  
*****
```

```
39 KO      OUTPUT CONTROL VARIABLES  
          IPRNT      5  PRINT CONTROL  
          IPLOT      0  PLOT CONTROL  
          QSCAL      0.  HYDROGRAPH PLOT SCALE  
          IPNCH      0  PUNCH COMPUTED HYDROGRAPH  
          IOUT       22  SAVE HYDROGRAPH ON THIS UNIT  
          ISAV1      1  FIRST ORDINATE PUNCHED OR SAVED  
          ISAV2     310  LAST ORDINATE PUNCHED OR SAVED  
          TIMINT     0.083  TIME INTERVAL IN HOURS
```

.....

```
*****  
*      *  
43 KK  *  SUM1   *  
*      *  
*****
```

```
45 KO      OUTPUT CONTROL VARIABLES  
          IPRNT      5  PRINT CONTROL  
          IPLOT      0  PLOT CONTROL  
          QSCAL      0.  HYDROGRAPH PLOT SCALE  
          IPNCH      0  PUNCH COMPUTED HYDROGRAPH  
          IOUT       22  SAVE HYDROGRAPH ON THIS UNIT  
          ISAV1      1  FIRST ORDINATE PUNCHED OR SAVED  
          ISAV2     310  LAST ORDINATE PUNCHED OR SAVED  
          TIMINT     0.083  TIME INTERVAL IN HOURS
```

.....

```
*****  
*      *  
47 KK  *  RTE1   *  
*      *  
*****
```

```
49 KO      OUTPUT CONTROL VARIABLES  
          IPRNT      5  PRINT CONTROL  
          IPLOT      0  PLOT CONTROL  
          QSCAL      0.  HYDROGRAPH PLOT SCALE  
          IPNCH      0  PUNCH COMPUTED HYDROGRAPH  
          IOUT       22  SAVE HYDROGRAPH ON THIS UNIT  
          ISAV1      1  FIRST ORDINATE PUNCHED OR SAVED  
          ISAV2     310  LAST ORDINATE PUNCHED OR SAVED  
          TIMINT     0.083  TIME INTERVAL IN HOURS
```

.....

```
*****  
*      *  
51 KK  *  SHED10 *  
*      *  
*****
```

```
53 KO      OUTPUT CONTROL VARIABLES  
          IPRNT      5  PRINT CONTROL  
          IPLOT      0  PLOT CONTROL
```


QSCAL 0. HYDROGRAPH PLOT SCALE
IPNCH 0 PUNCH COMPUTED HYDROGRAPH
IOUT 22 SAVE HYDROGRAPH ON THIS UNIT
ISAV1 1 FIRST ORDINATE PUNCHED OR SAVED
ISAV2 310 LAST ORDINATE PUNCHED OR SAVED
TIMINT 0.083 TIME INTERVAL IN HOURS

.....

* *
57 KK * SUM2 *
* *

59 KO OUTPUT CONTROL VARIABLES
IPRNT 5 PRINT CONTROL
IPLOT 0 PLOT CONTROL
QSCAL 0. HYDROGRAPH PLOT SCALE
IPNCH 0 PUNCH COMPUTED HYDROGRAPH
IOUT 22 SAVE HYDROGRAPH ON THIS UNIT
ISAV1 1 FIRST ORDINATE PUNCHED OR SAVED
ISAV2 310 LAST ORDINATE PUNCHED OR SAVED
TIMINT 0.083 TIME INTERVAL IN HOURS

.....

* *
61 KK * RTE2 *
* *

63 KO OUTPUT CONTROL VARIABLES
IPRNT 5 PRINT CONTROL
IPLOT 0 PLOT CONTROL
QSCAL 0. HYDROGRAPH PLOT SCALE
IPNCH 0 PUNCH COMPUTED HYDROGRAPH
IOUT 22 SAVE HYDROGRAPH ON THIS UNIT
ISAV1 1 FIRST ORDINATE PUNCHED OR SAVED
ISAV2 310 LAST ORDINATE PUNCHED OR SAVED
TIMINT 0.083 TIME INTERVAL IN HOURS

.....

* *
65 KK * SHED8 *
* *

67 KO OUTPUT CONTROL VARIABLES
IPRNT 5 PRINT CONTROL
IPLOT 0 PLOT CONTROL
QSCAL 0. HYDROGRAPH PLOT SCALE
IPNCH 0 PUNCH COMPUTED HYDROGRAPH
IOUT 22 SAVE HYDROGRAPH ON THIS UNIT
ISAV1 1 FIRST ORDINATE PUNCHED OR SAVED
ISAV2 310 LAST ORDINATE PUNCHED OR SAVED
TIMINT 0.083 TIME INTERVAL IN HOURS

```
*****
*   *
* SHED 9 *
*   *
*****
```

```
73 KO      OUTPUT CONTROL VARIABLES
          IPRNT      5   PRINT CONTROL
          IPLOT      0   PLOT CONTROL
          QSCAL      0.   HYDROGRAPH PLOT SCALE
          IPNCH      0   PUNCH COMPUTED HYDROGRAPH
          IOUT       22  SAVE HYDROGRAPH ON THIS UNIT
          ISAV1      1   FIRST ORDINATE PUNCHED OR SAVED
          ISAV2     310  LAST ORDINATE PUNCHED OR SAVED
          TIMINT     0.083 TIME INTERVAL IN HOURS
```

```
*****
*   *
* SHED12 *
*   *
*****
```

```
79 KO      OUTPUT CONTROL VARIABLES
          IPRNT      5   PRINT CONTROL
          IPLOT      0   PLOT CONTROL
          QSCAL      0.   HYDROGRAPH PLOT SCALE
          IPNCH      0   PUNCH COMPUTED HYDROGRAPH
          IOUT       22  SAVE HYDROGRAPH ON THIS UNIT
          ISAV1      1   FIRST ORDINATE PUNCHED OR SAVED
          ISAV2     310  LAST ORDINATE PUNCHED OR SAVED
          TIMINT     0.083 TIME INTERVAL IN HOURS
```

```
*****
*   *
* BNDY   *
*   *
*****
```

```
85 KO      OUTPUT CONTROL VARIABLES
          IPRNT      5   PRINT CONTROL
          IPLOT      0   PLOT CONTROL
          QSCAL      0.   HYDROGRAPH PLOT SCALE
          IPNCH      0   PUNCH COMPUTED HYDROGRAPH
          IOUT       22  SAVE HYDROGRAPH ON THIS UNIT
          ISAV1      1   FIRST ORDINATE PUNCHED OR SAVED
          ISAV2     310  LAST ORDINATE PUNCHED OR SAVED
          TIMINT     0.083 TIME INTERVAL IN HOURS
```

RUNOFF SUMMARY
FLOW IN CUBIC FEET PER SECOND
TIME IN HOURS, AREA IN SQUARE MILES

OPERATION	STATION	PEAK FLOW	TIME OF PEAK 6-HOUR	AVERAGE FLOW FOR MAXIMUM PERIOD	BASIN AREA	MAXIMUM STAGE	TIME OF MAX STAGE
24-HOUR	72-HOUR						
HYDROGRAPH AT SHED W	120.	10.17	28.	11.	10.	0.16	
HYDROGRAPH AT SHED11	40.	10.00	7.	3.	3.	0.02	
2 COMBINED AT SUM1	146.	10.08	35.	14.	13.	0.18	

C:\HAESTAD\GHEC1\SAMPLE\PLYMPST.OUT

ROUTED TO RTE1	145.	10.17	35.	14.	13.	0.18
HYDROGRAPH AT SHED10	40.	10.00	7.	3.	2.	0.02
2 COMBINED AT SUM2	167.	10.08	41.	16.	15.	0.20
ROUTED TO RTE2	165.	10.17	41.	16.	15.	0.20
HYDROGRAPH AT SHED8	73.	10.00	13.	5.	5.	0.04
HYDROGRAPH AT SHED 9	100.	10.00	18.	8.	7.	0.06
HYDROGRAPH AT SHED12	29.	10.00	5.	2.	2.	0.02
4 COMBINED AT BNDY	351.	10.08	78.	32.	29.	

0.31

SUMMARY OF KINEMATIC WAVE - MUSKINGUM-CUNGE ROUTING
(FLOW IS DIRECT RUNOFF WITHOUT BASE FLOW)

I STAQ	ELEMENT	DT	PEAK	TIME TO PEAK	VOLUME	DT	INTERPOLATED TO COMPUTATION INTERVAL		VOLUME
							PEAK	TIME TO PEAK	
		(MIN)	(CFS)	(MIN)	(IN)	(MIN)	(CFS)	(MIN)	(IN)
RTE1	MANE	3.96	145.63	609.47	2.88	5.00	144.82	610.00	2.88

CONTINUITY SUMMARY (AC-FT) - INFLOW=0.2718E+02 EXCESS=0.0000E+00 OUTFLOW=0.2718E+02 BASIN STORAGE=0.1137E-02 PERCENT ERROR= 0.0

RTE2	MANE	3.26	165.80	608.78	3.08	5.00	165.32	610.00	3.08
------	------	------	--------	--------	------	------	--------	--------	------

CONTINUITY SUMMARY (AC-FT) - INFLOW=0.3248E+02 EXCESS=0.0000E+00 OUTFLOW=0.3248E+02 BASIN STORAGE=0.7374E-03 PERCENT ERROR= 0.0

*** NORMAL END OF HEC-1 ***

POST-PROJECT W/ DETENTION

HEC1 S/N: 1343001909 HWVersion: 6.33 Data File: C:\HAESTAD\GHEC1\SAMPLE\PLYMD1.OUT
 C:\HAESTAD\GHEC1\SAMPLE\PLYMD1.OUT
 C:\WINDOWS\TEMP\vbh3C65.TMP

```

*****
* FLOOD HYDROGRAPH PACKAGE (HEC-1) *
*   MAY 1991 *
*   VERSION 4.0.1R *
* RUN DATE 01/24/2004 TIME 15:45:05 *
*****
    
```

```

*****
* U.S. ARMY CORPS OF ENGINEERS *
* HYDROLOGIC ENGINEERING CENTER *
*   609 SECOND STREET *
*   DAVIS, CALIFORNIA 95616 *
*   (916) 756-1104 *
*****
    
```

```

X   X   XXXXXXXX   XXXXX   X
X   X   X   X   X   X   XX
X   X   X   X   X   X   X
XXXXXXXX XXXX   X   XXXXX   X
X   X   X   X   X   X   X
X   X   X   X   X   X   X
X   X   XXXXXXXX   XXXXX   XXX
    
```

```

*****
* Full Microcomputer Implementation *
*   by *
*   Haestad Methods, Inc. *
*****
    
```

37 Brookside Road * Waterbury, Connecticut 06708 * (203) 755-1666

THIS PROGRAM REPLACES ALL PREVIOUS VERSIONS OF HEC-1 KNOWN AS HEC1 (JAN 73), HEC1GS, HEC1DB, AND HEC1KW.
 THE DEFINITIONS OF VARIABLES -RTIMP- AND -RTIOR- HAVE CHANGED FROM THOSE USED WITH THE 1973-STYLE INPUT STRUCTURE.
 THE DEFINITION OF -AMSKK- ON RM-CARD WAS CHANGED WITH REVISIONS DATED 28 SEP 81. THIS IS THE FORTRAN77 VERSION
 NEW OPTIONS: DAMBREAK OUTFLOW SUBMERGENCE, SINGLE EVENT DAMAGE CALCULATION, DSS:WRITE STAGE FREQUENCY,
 DSS:READ TIME SERIES AT DESIRED CALCULATION INTERVAL, LOSS RATE:GREEN AND AMPT INFILTRATION
 KINEMATIC WAVE; NEW FINITE DIFFERENCE ALGORITHM

LINE	ID	1	2	3	4	5	6	7	8	9	10
1	ID	100-YEAR POST-PROJECT RUNOFF FOR NORTH AREA W/ DET									
2	IT	5	310								
3	IO	5	0								
4	KK	SHED W									
5	KN	OFFSITE AREA, W. OF HWY 49									
6	KO	22									
7	BA	0.1563									
8	PB	5.31									
9	IN	6									
10	PC	0.0000	0.00174	0.00348	0.00522	0.00697	0.00871	0.01046	0.01220	0.01395	0.01570
11	PC	0.0174	0.01920	0.02095	0.02270	0.02446	0.02621	0.02797	0.02972	0.03148	0.03324
12	PC	0.0350	0.03677	0.03858	0.04041	0.04227	0.04416	0.04608	0.04803	0.05001	0.05201
13	PC	0.0540	0.05611	0.05821	0.06033	0.06248	0.06466	0.06687	0.06911	0.07138	0.07367
14	PC	0.0760	0.07835	0.08070	0.08307	0.08545	0.08784	0.09024	0.09265	0.09507	0.09751
15	PC	0.1000	0.10241	0.10487	0.10735	0.10984	0.11234	0.11485	0.11737	0.11990	0.12245
16	PC	0.1250	0.12761	0.13034	0.13317	0.13610	0.13915	0.14230	0.14557	0.14894	0.15241
17	PC	0.1560	0.15966	0.16334	0.16706	0.17082	0.17460	0.17842	0.18226	0.18614	0.19006
18	PC	0.1940	0.19817	0.20275	0.20775	0.21317	0.21900	0.22523	0.23185	0.23885	0.24623
19	PC	0.2540	0.26233	0.27139	0.28119	0.29173	0.30300	0.31942	0.34542	0.38784	0.46316

20	PC	0.5150	0.53220	0.54760	0.56120	0.57300	0.58300	0.59188	0.60032	0.60832	0.61588
21	PC	0.6230	0.62982	0.63648	0.64298	0.64932	0.65550	0.66152	0.66738	0.67308	0.67862
22	PC	0.6840	0.68925	0.69440	0.69945	0.70440	0.70925	0.71400	0.71865	0.72320	0.72765
23	PC	0.7320	0.73625	0.74040	0.74445	0.74840	0.75225	0.75600	0.75965	0.76320	0.76665
24	PC	0.7700	0.77329	0.77656	0.77981	0.78304	0.78625	0.78944	0.79261	0.79576	0.79889
25	PC	0.8020	0.80509	0.80816	0.81121	0.81424	0.81725	0.82024	0.82321	0.82616	0.82909
26	PC	0.8320	0.83489	0.83776	0.84061	0.84344	0.84625	0.84904	0.85181	0.85456	0.85729
27	PC	0.8600	0.86269	0.86536	0.86801	0.87064	0.87325	0.87584	0.87841	0.88096	0.88349
28	PC	0.8860	0.88849	0.89096	0.89341	0.89584	0.89825	0.90064	0.90301	0.90536	0.90769
29	PC	0.9100	0.91229	0.91456	0.91681	0.91904	0.92125	0.92344	0.92561	0.92776	0.92989
30	PC	0.9320	0.93409	0.93616	0.93821	0.94024	0.94225	0.94424	0.94621	0.94816	0.95009
31	PC	0.9520	0.95389	0.95576	0.95761	0.95944	0.96125	0.96304	0.96481	0.96656	0.96829
32	PC	0.9700	0.97169	0.97336	0.97501	0.97664	0.97825	0.97984	0.98141	0.98296	0.98449
33	PC	0.9860	0.98749	0.98896	0.99041	0.99184	0.99325	0.99464	0.99601	0.99736	0.99869
34	PC	1.0000	1.00000	1.00000	1.00000	1.00000					

35	LS			74							
36	UD	0.255									
37	KK	SHED11									
38	KM										
39	KO					22					
40	BA	.0209									
41	LS		96								
42	UD	0.1									
43	KK	SUM1									
44	KM										
45	KO					22					
46	HC	2									

HEC-1 INPUT

LINE	ID	1	2	3	4	5	6	7	8	9	10
47	KK	RTE1									
48	KM	ESTIMATED SECTION - USE 36" HDPE									
49	KO					22					
50	RD	1400	.01	.013		CIRC		3			
51	KK	SHED10									
52	KM										
53	KO					22					
54	BA	.0205									
55	LS		96								
56	UD	0.15									
57	KK	SUM2									
58	KM										
59	KO					22					
60	HC	2									
61	KK	RTE2									
62	KM	ESTIMATED SECTION - USE 36" HDPE									
63	KO					22					
64	RD	1100	.008	.013		CIRC		3			
65	KK	SHED8									
66	KM										
67	KO					22					
68	BA	.0419									
69	LS		96								
70	UD	.15									
71	KK	SHED 9									
72	KM										
73	KO					22					
74	BA	.0578									
75	LS		96								
76	UD	0.15									
77	KK	Node15									
78	KM										
79	KO					22					
80	HC	2									
81	KK	DET1									
82	KM	DETENTION ROUTING; MODIFY EX. POND; F.L. OUT 1045; C.L. OUT 1046.5; 6 SQ. FT.									

83 KO
 84 RS 1 STOR 0
 85 SA .1 1.3 1.5 1.85
 86 SE 1045 1050 1051 1051.5
 87 SL 1046.5 6 .6 .5
 88 SS 1051.3 20 3 1.5

HEC-1 INPUT

PAGE 3

LINE ID.....1.....2.....3.....4.....5.....6.....7.....8.....9.....10

89 KK SHED12
 90 KM
 91 KO 22
 92 BA .0169
 93 LS 96
 94 UD .15
 95 KK BNDY
 96 KM COMBINED RUNOFF @ APPROX. PROJECT BOUNDARY
 97 KO 22
 98 HC 3
 99 ZZ

ECI S/N: 1343001909 HMVersion: 6.33 Data File:
 C:\WINDOWS\TEMP\vbh3CG5.TMP

```
*****
* FLOOD HYDROGRAPH PACKAGE (HEC-1) *
* MAY 1991 *
* VERSION 4.0.1E *
* RUN DATE 01/24/2004 TIME 15:45:05 *
*****
```

```
*****
* U.S. ARMY CORPS OF ENGINEERS *
* HYDROLOGIC ENGINEERING CENTER *
* 609 SECOND STREET *
* DAVIS, CALIFORNIA 95616 *
* (916) 756-1104 *
*****
```

100-YEAR POST-PROJECT RUNOFF FOR NORTH AREA W/ DET

3 IO OUTPUT CONTROL VARIABLES
 IPRNT 5 PRINT CONTROL
 IPLOT 0 PLOT CONTROL
 QSCAL 0. HYDROGRAPH PLOT SCALE

IT HYDROGRAPH TIME DATA
 NMNIN 5 MINUTES IN COMPUTATION INTERVAL
 IDATE 1 0 STARTING DATE
 ITIME 0000 STARTING TIME
 NQ 310 NUMBER OF HYDROGRAPH ORDINATES
 NDDATE 2 0 ENDING DATE
 NDDTIME 0145 ENDING TIME
 ICENT 19 CENTURY MARK

COMPUTATION INTERVAL 0.08 HOURS
 TOTAL TIME BASE 25.75 HOURS

ENGLISH UNITS
 DRAINAGE AREA SQUARE MILES
 PRECIPITATION DEPTH INCHES
 LENGTH, ELEVATION FEET
 FLOW CUBIC FEET PER SECOND
 STORAGE VOLUME ACRE-Feet
 SURFACE AREA ACRES
 TEMPERATURE DEGREES FAHRENHEIT

```
*****
* 4 KK SHED W *
*****
```

6 KO OUTPUT CONTROL VARIABLES
 IPRNT 5 PRINT CONTROL
 IPL0T 0 PLOT CONTROL
 QSCAL 0. HYDROGRAPH PLOT SCALE
 IPNCH 0 PUNCH COMPUTED HYDROGRAPH
 IOUT 22 SAVE HYDROGRAPH ON THIS UNIT
 ISAV1 1 FIRST ORDINATE PUNCHED OR SAVED
 ISAV2 310 LAST ORDINATE PUNCHED OR SAVED
 TIMINT 0.083 TIME INTERVAL IN HOURS

37 KK *****
 * *
 * SHED11 *
 * *

39 KO OUTPUT CONTROL VARIABLES
 IPRNT 5 PRINT CONTROL
 IPL0T 0 PLOT CONTROL
 QSCAL 0. HYDROGRAPH PLOT SCALE
 IPNCH 0 PUNCH COMPUTED HYDROGRAPH
 IOUT 22 SAVE HYDROGRAPH ON THIS UNIT
 ISAV1 1 FIRST ORDINATE PUNCHED OR SAVED
 ISAV2 310 LAST ORDINATE PUNCHED OR SAVED
 TIMINT 0.083 TIME INTERVAL IN HOURS

43 KK *****
 * *
 * SUM1 *
 * *

45 KO OUTPUT CONTROL VARIABLES
 IPRNT 5 PRINT CONTROL
 IPL0T 0 PLOT CONTROL
 QSCAL 0. HYDROGRAPH PLOT SCALE
 IPNCH 0 PUNCH COMPUTED HYDROGRAPH
 IOUT 22 SAVE HYDROGRAPH ON THIS UNIT
 ISAV1 1 FIRST ORDINATE PUNCHED OR SAVED
 ISAV2 310 LAST ORDINATE PUNCHED OR SAVED
 TIMINT 0.083 TIME INTERVAL IN HOURS

47 KK *****
 * *
 * RTE1 *
 * *

49 KO OUTPUT CONTROL VARIABLES
 IPRNT 5 PRINT CONTROL
 IPL0T 0 PLOT CONTROL
 QSCAL 0. HYDROGRAPH PLOT SCALE
 IPNCH 0 PUNCH COMPUTED HYDROGRAPH
 IOUT 22 SAVE HYDROGRAPH ON THIS UNIT
 ISAV1 1 FIRST ORDINATE PUNCHED OR SAVED
 ISAV2 310 LAST ORDINATE PUNCHED OR SAVED

TIMINT 0.083 TIME INTERVAL IN HOURS

.....

* *
51 KK * SHED10 *
* *

53 KO OUTPUT CONTROL VARIABLES
IPRNT 5 PRINT CONTROL
IPLOT 0 PLOT CONTROL
QSCAL 0. HYDROGRAPH PLOT SCALE
IPNCH 0 PUNCH COMPUTED HYDROGRAPH
IOUT 22 SAVE HYDROGRAPH ON THIS UNIT
ISAV1 1 FIRST ORDINATE PUNCHED OR SAVED
ISAV2 310 LAST ORDINATE PUNCHED OR SAVED
TIMINT 0.083 TIME INTERVAL IN HOURS

.....

* *
57 KK * SUM2 *
* *

59 KO OUTPUT CONTROL VARIABLES
IPRNT 5 PRINT CONTROL
IPLOT 0 PLOT CONTROL
QSCAL 0. HYDROGRAPH PLOT SCALE
IPNCH 0 PUNCH COMPUTED HYDROGRAPH
IOUT 22 SAVE HYDROGRAPH ON THIS UNIT
ISAV1 1 FIRST ORDINATE PUNCHED OR SAVED
ISAV2 310 LAST ORDINATE PUNCHED OR SAVED
TIMINT 0.083 TIME INTERVAL IN HOURS

.....

* *
61 KK * RTE2 *
* *

63 KO OUTPUT CONTROL VARIABLES
IPRNT 5 PRINT CONTROL
IPLOT 0 PLOT CONTROL
QSCAL 0. HYDROGRAPH PLOT SCALE
IPNCH 0 PUNCH COMPUTED HYDROGRAPH
IOUT 22 SAVE HYDROGRAPH ON THIS UNIT
ISAV1 1 FIRST ORDINATE PUNCHED OR SAVED
ISAV2 310 LAST ORDINATE PUNCHED OR SAVED
TIMINT 0.083 TIME INTERVAL IN HOURS

.....

* *

65 KK * SHED8 *
* *

67 KO OUTPUT CONTROL VARIABLES
IPRNT 5 PRINT CONTROL
IPLOT 0 PLOT CONTROL
QSCAL 0. HYDROGRAPH PLOT SCALE
IPNCH 0 PUNCH COMPUTED HYDROGRAPH
IOUT 22 SAVE HYDROGRAPH ON THIS UNIT
ISAV1 1 FIRST ORDINATE PUNCHED OR SAVED
ISAV2 310 LAST ORDINATE PUNCHED OR SAVED
TIMINT 0.083 TIME INTERVAL IN HOURS

.....

* *
71 KK * SHED 9 *
* *

73 KO OUTPUT CONTROL VARIABLES
IPRNT 5 PRINT CONTROL
IPLOT 0 PLOT CONTROL
QSCAL 0. HYDROGRAPH PLOT SCALE
IPNCH 0 PUNCH COMPUTED HYDROGRAPH
IOUT 22 SAVE HYDROGRAPH ON THIS UNIT
ISAV1 1 FIRST ORDINATE PUNCHED OR SAVED
ISAV2 310 LAST ORDINATE PUNCHED OR SAVED
TIMINT 0.083 TIME INTERVAL IN HOURS

.....

* *
77 KK * Node15 *
* *

79 KO OUTPUT CONTROL VARIABLES
IPRNT 5 PRINT CONTROL
IPLOT 0 PLOT CONTROL
QSCAL 0. HYDROGRAPH PLOT SCALE
IPNCH 0 PUNCH COMPUTED HYDROGRAPH
IOUT 22 SAVE HYDROGRAPH ON THIS UNIT
ISAV1 1 FIRST ORDINATE PUNCHED OR SAVED
ISAV2 310 LAST ORDINATE PUNCHED OR SAVED
TIMINT 0.083 TIME INTERVAL IN HOURS

.....

* *
81 KK * DET1 *
* *

83 KO OUTPUT CONTROL VARIABLES
IPRNT 5 PRINT CONTROL
IPLOT 0 PLOT CONTROL
QSCAL 0. HYDROGRAPH PLOT SCALE
IPNCH 0 PUNCH COMPUTED HYDROGRAPH
IOUT 22 SAVE HYDROGRAPH ON THIS UNIT

ISAV1 1 FIRST ORDINATE PUNCHED OR SAVED
 ISAV2 310 LAST ORDINATE PUNCHED OR SAVED
 TIMINT 0.083 TIME INTERVAL IN HOURS

89 KK *****
 * *
 * SHED12 *
 * *

91 KO OUTPUT CONTROL VARIABLES
 IPRINT 5 PRINT CONTROL
 IPLOT 0 PLOT CONTROL
 QSCAL 0. HYDROGRAPH PLOT SCALE
 IPNCH 0 PUNCH COMPUTED HYDROGRAPH
 IOUT 22 SAVE HYDROGRAPH ON THIS UNIT
 ISAV1 1 FIRST ORDINATE PUNCHED OR SAVED
 ISAV2 310 LAST ORDINATE PUNCHED OR SAVED
 TIMINT 0.083 TIME INTERVAL IN HOURS

95 KK *****
 * *
 * BNDY *
 * *

97 KO OUTPUT CONTROL VARIABLES
 IPRINT 5 PRINT CONTROL
 IPLOT 0 PLOT CONTROL
 QSCAL 0. HYDROGRAPH PLOT SCALE
 IPNCH 0 PUNCH COMPUTED HYDROGRAPH
 IOUT 22 SAVE HYDROGRAPH ON THIS UNIT
 ISAV1 1 FIRST ORDINATE PUNCHED OR SAVED
 ISAV2 310 LAST ORDINATE PUNCHED OR SAVED
 TIMINT 0.083 TIME INTERVAL IN HOURS

RUNOFF SUMMARY
 FLOW IN CUBIC FEET PER SECOND
 TIME IN HOURS, AREA IN SQUARE MILES

OPERATION	STATION	PEAK FLOW	TIME OF PEAK 6-HOUR	AVERAGE FLOW FOR MAXIMUM PERIOD			BASIN AREA	MAXIMUM STAGE	TIME OF MAX STAGE
24-HOUR	72-HOUR								
HYDROGRAPH AT SHED W	120.	10.17	28.	11.	10.	0.16			
HYDROGRAPH AT SHED11	40.	10.00	7.	3.	3.	0.02			
2 COMBINED AT SUM1	146.	10.08	35.	14.	13.	0.18			
ROUTED TO RTE1	142.	10.08	35.	14.	13.	0.18			
HYDROGRAPH AT SHED10	36.	10.00	7.	3.	2.	0.02			
2 COMBINED AT SUM2	177.	10.08	41.	16.	15.	0.20			
ROUTED TO RTE2	172.	10.08	41.	16.	15.	0.20			
HYDROGRAPH AT SHED8	73.	10.00	13.	5.	5.	0.04			
HYDROGRAPH AT SHED 9	100.	10.00	18.	8.	7.	0.06			
2 COMBINED AT Node15	173.	10.00	32.	13.	12.	0.10			

ROUTED TO							
DET1	62.	10.42	32.	13.	12.	0.10	
1051.06	10.42						
HYDROGRAPH AT							
SHED12	29.	10.00	5.	2.	2.	0.02	
3 COMBINED AT							
RNDY	257.	10.08	78.	31.	29.		
0.31							

SUMMARY OF KINEMATIC WAVE - MUSKINGUM-CUNGE ROUTING
(FLOW IS DIRECT RUNOFF WITHOUT BASE FLOW)

ISTAQ	ELEMENT	DT	PEAK	TIME TO PEAK	VOLUME	DT	INTERPOLATED TO COMPUTATION INTERVAL		VOLUME
							PEAK	TIME TO PEAK	
		(MIN)	(CFS)	(MIN)	(IN)	(MIN)	(CFS)	(MIN)	(IN)
RTE1	MANE	1.59	145.18	607.48	2.88	5.00	142.17	605.00	2.88
CONTINUITY SUMMARY (AC-FT) - INFLOW=0.2718E+02 EXCESS=0.0000E+00 OUTFLOW=0.2718E+02 BASIN STORAGE=0.1929E-03 PERCENT ERROR= 0.0									
RTE2	MANE	1.32	174.96	606.69	3.08	5.00	171.90	605.00	3.08
CONTINUITY SUMMARY (AC-FT) - INFLOW=0.3248E+02 EXCESS=0.0000E+00 OUTFLOW=0.3248E+02 BASIN STORAGE=0.1512E-03 PERCENT ERROR= 0.0									

*** NORMAL END OF HEC-1 ***

